




How to Write an Approvable Stormwater Pollution Prevention Plan (SWPPP)

Mell Nevils (PE, CPESC, CESSWI)
Stormwater Plan Review & Inspector
Howard County Soil & Water Conservation District

Sarah Brichford (CPESC, CPSWQ)
Stormwater Technician
Howard County Stormwater District

The SWPPP designer should provide all of the information needed by the plan reviewer in an organized format that is easy to access and determine if adequate.

- ✓ all required elements including Rule 5 (SWPPP Parts A, B, C) and any local ordinance requirements
- ✓ clear instructions and details for contractor



A SWPPP should include:

- Construction sequence and brief project description
- Erosion and sediment controls to be used during construction
- Pollution prevention and good housekeeping measures
- Post-construction stormwater controls (if required)
- Index to all required elements

A plan design process . . .



Construction Sequence

- Should be unique to the site – *what is this project?*
 - sensitive areas, wetlands, water features
- Should clearly describe basic sequence of events
- Few sentences for a simple plan
- Several paragraphs for a complex plan

(cont.) Construction Sequence

- Pre-construction meeting in advance of any land disturbing activity
 - Site owner, plan designer, contractor, site inspector
- Clearing / grading plan
- Installation of erosion and sediment controls
- Construction phase: start to finish
- Final stabilization of site
- Removal of temporary erosion and sediment controls

Erosion & sediment control

1. Identify the drainage pattern
2. Determine how construction will affect the drainage pattern
3. Identify the erosion and sediment control measures used
4. Provide details for each measure
5. Provide a sequence for installation of measures

Erosion and Sediment Control

1. Identify the Drainage Pattern

- Contours should be at adequate intervals to determine drainage patterns on the site
- Water features such as streams, ponds and wetlands should be identified.
 - on-site and off-site
- Contours may need to extend beyond the Limits of Disturbance or property lines to adequately show
 - on-site drainage
 - effects of disturbance on off-site properties (e.g. flooding)

Erosion and Sediment Control

2. Determine how the land disturbance and construction will affect the drainage pattern

- Limits of disturbance
- Changes in sheet flow
- Changes in concentrated flow
- Inlets and outlets

Erosion and Sediment Control

3. Identify sediment and erosion control measures

- Perimeter controls
 - Silt fence, silt socks, rock berms, compost berms
- Directing runoff
 - Diversions, channels, slope drains
- Erosion control
 - Matting/liners, stone stabilization

Erosion and Sediment Control

3. (cont.) Identify sediment and erosion control measures


- Sediment capture
 - Basins, traps, check dams (straw & rock), construction entrance/exits
- Inlet and outlet protection
 - Dandy bags, rock donuts, silt fence inlet protection, energy dissipaters
- Soil stockpiles
- Stabilization
 - temporary
 - permanent

4. BMP Details

- Each proposed BMP has a detail and/or schedule
- Dimensions are shown for each measure
- Required information is provided for BMP maintenance
 - During construction
 - Post construction

(cont.) BMP Details – Legends and Drawings

- Provide an accurate legend that contains symbols for all measures
- or**
- Call out each measure on the plan sheet



(cont.) BMP Details - maintenance

- SWPPP should include:
 - instructions on when maintenance is needed for each BMP
 - instructions on how to maintain each BMP
 - Operation & Maintenance (O&M) manuals attached for any post construction BMPs

Pollution Prevention & Good Housekeeping Material Handling

- Storage of fertilizer
- On-site vehicle maintenance
- Drip pans for equipment
- On-site fueling of equipment
- Fuel tanks

PPGH (cont.)

Material Handling

- Pesticides (including herbicides)
- Trash collection and disposal
- Concrete washout water and waste concrete
 - Concrete truck washout water
 - Water in the concrete washout BMP
 - Empty concrete bags

Post construction BMP specifications

- Description of the pollutants for the proposed project
 - What could be generated from this site?
- Determine the required design specification
 - Federal requirements
 - State requirements
 - Local requirements
- Provide documentation that your plan meets the requirements
 - Drainage calculations, sizing, etc.

Post Construction BMP specifications

- Design and locate each BMP to be sure it meets the requirement
- Maintenance requirements are:
 - adequate
 - understandable and practical
 - include a timeframe for maintenance
- Operation and Maintenance Manuals should be included for all post-construction BMPs

Index to Required SWPPP Elements

Table of contents referencing
IDEM Rule 5 elements and local
requirements

Guidance on Each of the 23 Basic Plan Elements:

A1 - Plan Index showing locations of required items

The plan index should include a list of the required items in the rule and where they are located on the site. The plan index should be included on the standard plan review checklist.

A2 - 11 X 17 inch plat showing building lot numbers/boundaries

The reduced size plat of the project is intended to be a basic representation of the project layout, and road names. It is not intended to be a complete representation of the County plat. The plat is primarily to provide staff a simplified layout of the project that can be used as a reference.

The plat should be legible, therefore based on the size of the project it is acceptable to use a smaller size plat.

(This item is not required for single-family residential developments of four lots or less.)

A3 - Narrative describing project nature and purpose:

The plan should include information regarding the nature and purpose of the project. The narrative should include other plan requirements.

A4 - Vicinity map showing project location:

The plan should include a map that depicts the site in relation to other areas in the county. The map should show the project site location. Acceptable map types include USGS topographic maps, county maps, or maps showing the site location.

A5 - Legal description of the project site:

The legal description of the project site should be identified to the nearest quarter section. Longitude and latitude coordinates are not a requirement of the plan; the checklist does not require them.

A6 - Location of all lots and proposed site improvements:

Lot boundaries and numbers are required to be shown on the plan. In addition, the plan should show roads (names, if available), structures, and common areas.

Single lot projects should show the location of any proposed structures.

A7 - Hydrologic unit code:

Index to Required SWPPP Elements

Plan sheet format
CAD file



**Rule 5 Checklist - Section A:
Construction Plan Elements**

1. Index Showing Location Of Required Plan Elements
Plan Elements A2-A23, B3-B35, & C1-C3 Are Addressed On This Sheet And Are As Follows:
(A) 22x17 Inch Plot With Building, Lot, Boundaries, Road Layout Lines
(B) 22x17 Inch Plot That Shall Be Submitted As A Separate Document To The Howard County Stormwater District
2. Narrative Describing Nature And Purpose Of Project
3. Narrative Map Showing Project Location
4. Legal Description Of The Project Site
5. Location Of All Site Imperviments
6. 24 Hour Hydrologic Unit Code
7. Note Any State Or Federal Water Quality Limits
8. Specific Points Where Storm Water Discharge Will Leave The Site
9. Location And Name Of All Wetlands, Lakes And Water Courses On And Adjacent To The Site
10. Identification Of All Receiving Waters
11. Identification Of Potential Discharges To Ground Water (Abandoned Well, Sinkhole, Etc.)
12. 100 Year Floodplain, Floodway, And Floodway Fringe
(See Attached Flood Insurance Rate Map. A Flood Insurance Rate Map Shall Be Submitted As A Separate Document To The Howard County Stormwater District.)
13. The Construction And Post Construction Estimate Of Peak Discharge (10 Year Storm Event) Note The Howard County Ordinance 2012-001: 13 The 100 Year Return Period Storm Of Critical Duration Shall Not Exceed 0.3 CFS Per Acre Of Development, The 10 Year Return Construction Peak Discharge (CFS) The 10 Year Post Construction Peak Discharge (CFS) The 100 Year Post Construction Peak Discharge (CFS) (Area) (Area) (Area)
14. Adjacent Land Use, Including Upstream Watershed
15. Construction Limits
(See Section Control Sheets) For Construction Limits
16. Identification Of Existing Vegetative Cover
17. Note Any State Or Federal Water Quality Limits
(See Attached Site Map. Flood Insurance Rate Map Shall Be Submitted As A Separate Document To The Howard County Stormwater District.) Limitations Are As Follows: (A) Locations, Size And Orientation Of Pressurized Storm Water Systems (e.g. Pumps, Sewers, And Channels)
18. Plans For Any Off-Site Construction Activities Associated With The Project (E.g., Underground Electric, Sewer, Water, Tele, Etc.)
19. Locations Of Proposed Soil Stockpiles, And/or Borrow Disposal Areas
20. Existing Site Topography At An Interval Appropriate To Indicate Drainage Patterns
(See Sheet C) For Existing Contours
21. Proposed Final Topography At An Interval Appropriate To Indicate Drainage Patterns
(See Sheet C) For Proposed Final Topography

**Rule 5 Checklist - Section B:
Stormwater Pollution Prevention Plan-Construction Component**

1. Description Of Potential Pollutant Source Associated With Construction Activities
The Following Shall Generate Potential Pollutants Associated With Construction Activities:
A. Fueling Of Vehicle
B. Leaking Equipment Or Vehicle
C. Material Storage
D. Site Erosion
E. Excavation Of Materials
F. Spilled Oils
G. Construction Waste And Litter
H. Sanitary Waste
I. Concrete Washout And Washout
J. Tracking Of Soil Offsite
2. Sequence Describing Stormwater Quality Measure Implementation Relative To Land Disturbing Activities
Reconstruction:
A. Notify Howard County Stormwater District At 703-456-2207
B. Contact The Indiana Underground Water Protection Services, Inc. To Verify The Location Of Any And All Underground Utilities
C. Contact Rule 5 Information At The Job Site. Contractor Shall Designate A Person Responsible For On-Site Inspections And For Providing The SWPPP On-Site. Copies Of The Inspections Shall Remain On-Site And Available For Review By The Howard County Stormwater District.
Construction:
A. Establish Construction Erosion Control
B. ()
3. State Construction Erosion Control Locations And Specifications (At All Points Of Ingress And Outgress)
The Contractor Shall Utilize Existing Streets And Drives As Much As Possible For Construction Ingress And Egress. The Contractor Shall Keep Public Roads And Private Drives Clear And Remove All Dirt, Debris And Other A Result Of Construction Activities. Temporary Construction Erosion Control Shall Meet The Requirements Of The Construction Good Practices As Stated On Sheet C.
4. Sediment Control Measures For Sheet Run Areas
5. Sediment Control Measures For Concentrated Flow Areas
6. Storm Sewer Inlet Protection Measure Locations And Specifications
7. Runoff Control Measures (e.g. Ditches, Rock Check Dams, Slope Drains, Etc.)
8. Stormwater Outlet Protection Specifications
9. Grade Stabilization Structure Locations And Specifications
10. Location, Dimensions, Specifications, And Construction Details Of Each Storm Water Quality Measure.
(See Sheet C) For Erosion Control Details And Erosion Control Sheets. For Placement Of Erosion Control Measures.
11. Temporary Surface Stabilization Methods Appropriate For Each Season (Including Seeding)
All Disturbed Areas Left Inactive For More Than 10 Days Require Temporary Seeding. (See Sheet C) For Seeding Details.
12. Permanent Surface Stabilization Specifications (Including Seeding)
All Disturbed Areas Require Permanent Seeding Upon Final Grading. (See Sheet C) For Seeding Details.
13. Material Handling And Spill Prevention Plan
Vehicle And Equipment Maintenance. Onsite Vehicle And Equipment Maintenance Should Only Be Used Where It Is Inevitable To Load Vehicle And Equipment Onsite For Maintenance And Repair. If Maintenance Must Occur Onsite, The Area Where Repairs Are To Be Made Must Be Located Away From Drainage Courses. Dip Pans And/or Absorbent Pads Should Be Used During Vehicle And Equipment Maintenance Work. That Involves Fluids, Leaks, The Maintenance Area Is Performed Over An Impermeable Surface In A Designated Maintenance Area. Inspect Onsite Vehicle And Equipment Daily At The Start-Up For Leaks, And Repair Immediately. Properly Dispose Of Used Oils, Fluids, Lubricants And Spill Cleanup Materials. Do Not Place Used Oil In A Dumpster Or Pour Into A Storm Drain Or Watercourse.
Vehicle Fueling. Onsite Vehicle And Equipment Fueling Should Only Be Used Where It Is Inevitable To Load Vehicle And Equipment Onsite For Fueling. Dip Pans And Absorbent Pads Should Be Used During Vehicle And Equipment Fueling. Unless The Fueling Is Performed Over An Impermeable Surface In A Designated Fueling Area, Fueling Used In Vehicle And Equipment Fueling Should Be Equipped With An Automatic Shut-Off To Control Dispensing Operations (Should Not Be Left Unattended). Federal, State, And Local Requirements Should Be Observed For Any Stationary Above Ground Storage Tanks.
Debris Collection. To Prevent Clogging Of The Storm Drainage System, Litter And Debris Removal From Drainage Ditches, Storm, Road, And Catch Lines Should Be A Priority. Construction Debris And Waste Should Be Removed From The Site Regularly Or More Frequently As Needed. Construction Material Intended To Be Public Should Be Stored In An Orderly Manner. Stormwater Runoff Should Be Prevented From Contacting Stored Solid Waste.
Concrete Washout. Perform Washout Of Concrete Trucks Offsite Or In Designated Area Only. Do Not Wash Out Concrete Trucks Into Storm Drains, Open Ditches, Streams Or Drains. Do Not Allow Excess Concrete To Be Dumped On Site, Except In Designated Area.
For On-Site Washout. Locate Washout Area At Least Fifty (50) Feet From Storm Drains, Open Ditches Or Bodies Of Water. Do Not Allow Runoff From This Area By Constructing A Temporary Basin Or Holding Area Large Enough For Loads And Solid Waste Wash-Out Wastes Into The Designated Area Where The Concrete Can Set And Be Broken-Up And Then Deposited Of Property.

Rule 5 Checklist - Section B: (Continued)

13. Material Handling And Spill Prevention Plan (Continued)
Material Handling For Soils. In The Event Of A Material Spill (Fuel, Oil, Fluids, Lubricants, Etc.) Denigrate The Area Allowing No Vehicle To Enter Or Leave The Spill Zone. Notify The Indiana Department Of Environmental Management (IDEM), Office Of Emergency Response, By Calling The Appropriate Phone Number. (IDEM: 317-233-7343 Or Toll Free: 800-233-7345. Also, The National Response Center At 800-424-6602 And Provide The Following Information: Time Of Observation Of The Spill, Location Of The Spill, Identify Material Spilled, Possible Threat And Source Of Spill, Weather Conditions, Personnel On Site And Action Initiated By Personnel. Notify The Local Fire Department And Police Department And The Howard County Stormwater District At 703-456-2207. Use State And Indiana Cleanup Unit. The Situation Has Been Reported And The Spill Has Been Eliminated.
14. Monitoring And Maintenance Guidelines For Each Proposed Storm Water Quality Measure
The Contractor Shall Maintain All Water Quality Measures During Construction To Prevent Any Blockages From Accumulated Sediment. Monitoring Of The Protective Measures Shall Be Done On A Weekly Basis And Again Within 24 Hours Of Every Rainfall Run-Event.
Maintenance shall include a written record of each inspection that is made within 24 hours of a rain event and weekly. The written record shall be made available upon request.
Temporary Construction Erosion Control (Erosion Control) Inspection Weekly, With In 24 Hours Of Every Half-Inch Rain Event, And After Heavy Rain.
A. Inspect And Repair As Needed.
B. Top Dress And As Needed.
C. Remove Immediately Any Mud And Sediment Tracked Or Washed Onto The Street Using Brushing Or Sweeping. Wash Area Once It Runoff Has Been Flowing Through A Sediment Trap.
D. Repair Any Damaged Pavement Immediately.
15. Inlet Protection (If Needed)
A. Replace If Torn, Starts To Degraded, Or Becomes Ineffective In Anyway.
B. Remove Sediment Accumulated Behind Each Dam As Needed To Maintain Channel Capacity. To Allow Drainage Through The Dam, And To Prevent Large Flow From Disrupting Sediment.
C. Add Aggregate To The Dams As Needed To Maintain Design Height And Cross Section.
D. When The Dams Are No Longer Needed, Remove The Aggregate And Restore Channel Using An Erosion Resistant Lining, If Necessary.
16. Inlet Protection (If Needed)
A. Inspect Daily And After Each Storm And Remove Sediment.
B. Replace Or Clean Sediment Filter As Needed.
C. Remove Tracked Sediment From Street (But Not By Flushing With Water) To Reduce The Sediment Load On Inlet Protection.
D. Check For And Repair Any Adjacent Erosion.
E. Repair Washed Out Areas.
17. Erosion Control Blanket (If Needed)
A. Repair And Filled As Needed.
B. Re-Check And Repair As Needed.
18. Temporary Seeding
A. Mow Or Limit To Reach Seeded Percent Coverage.
B. Fertilize As Needed.
C. Install Additional Erosion Control To Help Establish Cover.
Check And Maintain Any Additional Erosion Control Measures As Needed.
19. Erosion Control Specifications For Individual Building Lots.

**Rule 5 Checklist - Section C:
Storm Water Pollution Prevention Plan-Pool Construction Component**

1. Description Of Pollutants And Their Sources Associated With The Proposed Land Use
2. Sequence Describing Storm Water Quality Measure Implementation. (Provide A Sequence Of When The Proposed Post Construction Stormwater Quality Measure Will Be Installed.)
3. Description Of Proposed Post Construction Storm Water Quality Measures. How These Measures Will Reduce Discharge Of Suspended Solids And Meet The Requirements Of Flood Control Ordinance 2002-001-131
4. Location, Dimensions, Specifications, And Construction Details Of Each Storm Water Quality Measure
5. Description Of Maintenance Guidelines For Post Construction Storm Water Quality Measures

Pre-Construction Meeting Required
The Site Owner **Must** Schedule A Pre-construction Meeting At Least 48 Hours In Advance Of Land Disturbance. Please Contact The Stormwater Inspector At 765-457-2114 Ext. 107.

REVISIONS FOR APPROVAL:	DATE	AGENCY	LOC-1 LOC-2 LOC-3
DESIGNED: NAME	DRAWN: NAME		

PERSONNEL	DATE
PROJECT MANAGER	
PROJECT ENGINEER	
PROJECT SUPERVISOR	
PROJECT ASSISTANT	
PROJECT CLERK	

Discussion

Mell Nevils

Stormwater Plan Review & Inspector
Howard County Soil & Water Conservation District

Sarah Brichford

Stormwater Technician
Howard County Stormwater District